

BULK ITEM:	REQUIRED	EXISTING	PROPOSED
MIN. LOT AREA	3.0 AC.	2,424 AC. *	2,424 AC. *
MIN. LOT FRONTAGE	300 FT.	308.89 FT.	308.89 FT.
MAIN HOUSE:			
MIN. FRONT YARD (1)	100 FT.	100.25 FT.	100.25 FT.
MIN. REAR YARD	100 FT.	104.0 FT.	104.0 FT.
MIN. SIDE YARD (1)	100 FT.	58.0 FT. **	58.0 FT. **
MAX. BUILDING HEIGHT	2 1/2 STORIES 35 FT.	2 1/2 STORIES 34.0 FT.	2 1/2 STORIES 34.0 FT.
STUDIO:			
MIN. FRONT YARD	100 FT.	107.4 FT.	107.4 FT.
MIN. SIDE YARD	100 FT.	114.4 FT.	114.4 FT.
MAX. BUILDING HEIGHT	25 FT.	24.5 FT.	24.5 FT.
SHED:			
MIN. REAR YARD	100 FT.	21.1 FT. *	21.1 FT. *
MIN. SIDE YARD	100 FT.	177.5 FT.	177.5 FT.
MAX. BUILDING HEIGHT	25 FT.	15.0 FT.	15.0 FT.
GARAGE:			
MIN. REAR YARD	100 FT.	23.0 FT. *	23.0 FT. *
MIN. SIDE YARD	100 FT.	92.1 FT. *	92.1 FT. *
MAX. BUILDING HEIGHT	25 FT.	23.0 FT.	23.0 FT.
MAX. BUILDING COVERAGE (1)	3%	3.17% *	4.08% **
MAX. LOT COVERAGE (1)	10%	11.65% *	9.99%
BUILDING ENVELOPE RESTRICTION (1)	100 FT. x 100 FT. (SQUARE)	93.65' x 93.65' (SQUARE)	93.65' x 93.65' (SQUARE)

1. SUBJECT PROPERTY KNOWN AS LOT 11, BLOCK 26 AS SHOWN ON THE CURRENT TAX MAP (SHEET 15) OF THE TOWNSHIP OF HARDING, MORRIS COUNTY, NEW JERSEY.
2. BOUNDARY, LOCATION AND TOPOGRAPHIC INFORMATION FROM A SURVEY DONE BY THIS FIRM, DANIEL E. PARKER, N.J.P.L.S. LIC. NO. 35866, DATED MAY 2017, ELEVATIONS ARE BASED ON THE SEALED DATUM.
3. THE SUBJECT PROPERTY LIES WITHIN THE R-1 RURAL RESIDENTIAL ZONE AND THERE ARE NO ZONE BOUNDARIES WITHIN 200 FT. OF THE PROPERTY.
4. THE SUBJECT PROPERTY IS SERVED BY PRIVATE WELL FOR WATER SUPPLY AND AN INDIVIDUAL ON SITE SEPTIC DISPOSAL SYSTEM.
5. ARCHITECTURAL INFORMATION OBTAINED FROM PLANS PREPARED BY STUDIO 1200, LLC., P.O. NANCY DOUGHERTY, AIA.
6. THE SUBJECT PROPERTY LIES WITHIN FLOOD ZONE X - AREAS DETERMINED TO BE OUTSIDE THE 500 YEAR FLOODPLAIN.
7. NET DECREASE IN IMPERVIOUS COVERAGE = 1,746 S.F.
8. PROPOSED AREA OF DISTURBANCE = 24,089 S.F. (LESS THAN 1.0 Ac.) THEREFORE THIS DEVELOPMENT IS CLASSIFIED AS A MINOR PROJECT FOR THE PURPOSES OF STORMWATER MANAGEMENT.
9. ALL NEW UTILITY SERVICE(S) SHALL BE INSTALLED UNDERGROUND. THIS PLAN IS NOT GUARANTEED FOR ACCURACY FOR THE LOCATIONS OF EXIST. UNDERGROUND UTILITIES. THE USER SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATIONS OF ALL SUBSURFACE UTILITIES IN THE VICINITY OF THE PROJECT PRIOR TO THE BEGINNING OF ANY CONSTRUCTION. FOR MARKOUT, CALL 1-800-272-1000
10. LOT AREA = 105,611.22 S.F. OR 2.44 AC.
11. THE TOWNSHIP CODE REQUIRES THE INSTALLATION OF SOLID METAL GUTTER COVERS ON ALL W/OF ROOF AREAS TO DISCHARGE TO DRYWELLS. THE USE OF GUTTER HELMET AND GUTTER TOPPER PRODUCTS HAS BEEN APPROVED BY THE TOWNSHIP. THE USE OF OTHER PRODUCTS MUST BE APPROVED IN ADVANCE BY THE TOWNSHIP ENGINEER. SCREENS ARE NOT PERMISSIBLE.
12. THE SEPARATION BETWEEN THE EXTERIOR GRADE AND THE LOWEST STRUCTURAL MEMBER MUST BE AT LEAST 6".
13. THE CONSTRUCTION OF THE SEPTIC SYSTEM SHALL BE DONE IN ACCORDANCE WITH THE APPROVED SEPTIC SYSTEM DESIGN AS PREPARED BY THIS FIRM.
14. AN AREA OF AT LEAST 10 FT. WIDE AROUND THE FOUNDATION WILL BE GRADED DOWNWARD AWAY FROM THE FOUNDATION.
15. THE TOWNSHIP ENGINEER WILL BE NOTIFIED AT LEAST 72 HOURS IN ADVANCE OF THE INSTALLATION OF THE DRYWELLS OR ROOF DRAIN PIPING.
16. THE CONTRACTOR WILL ADD ADDITIONAL SOIL EROSION AND SEDIMENT CONTROL MEASURES AS DIRECTED BY THE TOWNSHIP ENGINEER
17. THE FOLLOWING SITE WORK INSPECTIONS ARE REQUIRED:
 - A. SILT FENCE (AFTER INSTALLATION)
 - B. ROOF DRAIN PIPES AND ROOF DRAINAGE PIPES (BEFORE BACKFILL)
 - C. SITE GRADING (AFTER VEGETATIVE STABILIZATION)
 - D. FINAL (AFTER VEGETATIVE STABILIZATION)
18. THERE ARE NO SLOPES IN EXCESS OF 15% ON THIS SITE THAT ARE PROPOSED TO BE DISTURBED.
19. AS PER THE N.J.D.E.P. GEOWEB WEBSITE THERE ARE NO WETLANDS WITHIN 150 FT. OF THE PROPOSED DISTURBANCE AREA, AND THERE ARE NO C-1 WATERWAYS WITHIN 300 FT. OF THE PROPOSED AREA OF DISTURBANCE.
20. IF THE ACTUAL LIMIT OF DISTURBANCE CREATED DURING THE CONSTRUCTION PROCESS EXCEEDS ONE ACRE, STORMWATER CONTROL CALCULATIONS COMPLYING WITH NJAC 7:8 MUST BE SUBMITTED.

MR. DAVID BRADY, ESQ.
BRADY & CORREALE, LLP
P.O. BOX 2136
MORRISTOWN, NJ 07962
PH: 973-267-3500

CHAIRMAN	DATE
SECRETARY	DATE
BOARD ENGINEER	DATE

[illegible]

88 Glen Alpin Road, LLC

HARDING TOWNSHIP, NJ
MORRIS COUNTY
BLOCK 26 - LOT 11
Zone: R-1

ZONING INFORMATION			
ZONE - R-1	REQUIRED	EXISTING	PROPOSED
LOT AREA MIN. (SQ. FT.)	130,680	105,611*	105,611*
LOT WIDTH MIN. (FT.)	300	308.75	308.75
YARD REQUIREMENTS (BUILDING)			
FRONT YARD MIN. (FT.)	100	40.35	106.34
SIDE YARD MIN. (FT.)	100	37.55	56.21(v)
REAR YARD MIN. (FT.)	100	22.44	22.44 (v)
MAX. LOT COVERAGE (%)	10% (13,067 sf.)	8.8% 9,345.92	9.9% 4,311.06
BUILDING AREA (SQ FT)	3%	3.14%*	4.08%**
MAXIMUM BUILDING AREA	3%	3.14%*	4.08%**
BUILDING HEIGHT (PRINCIPAL BLDG)	35 Ft (2.5 STORIES)	24.37 Ft	30.12 FT.
BUILDING HEIGHT (ACCESSORY BLDG)	25 Ft	NO CHANGE	NO CHANGE

(v) VARIANCE REQUIRED

* EXISTING NON-CONFORMING

** Approved per Resolution No. 1-00-Donald & Madeline Ploetner Adopted August 27, 2001

NOTES:

1. THE PROPOSED PROJECT DOES CONTAIN ANY AND WILL NOT DISTURB ANY FRESHWATER WETLANDS OR BOUNDARY AREAS.
2. NO FLOOD PLAIN LIMITS ARE PRESENT ON THE PROPERTY.


SCOPE OF WORK

It is the intention and meaning of these specifications to specify and secure all labor, materials, equipment, workmanship and supervision required for the installation of the work in accordance with the drawings and specifications and all else not necessarily shown nor mentioned, but which may be essential for a complete and workmanlike job as intended. Contractor is responsible to verify any planting or quantity lists on the plans. Any items contained within the plans shall be included in the contractor's scope of work unless otherwise specified. Prices shall include all operations and permits necessary for the construction and installation as specified on the drawings and herein.

CONSTRUCTION NOTES:

1. Contractor shall obtain and be responsible for all permits and inspections. All work shall be performed in accordance with the IRC 2018 New Jersey Edition, and Township of Harding. All work shall be in compliance with all Federal, State, County, and Local regulations and ordinances. Contractor shall follow and be guided by Soil Conservation Service regulations.
2. Once the construction permit is issued by Federal, State or Municipal officials, the landscape architect shall not be responsible for any changes to the scope of work, alterations to the project, materials specified, site furnishings, drainage design, guard rails or hand rails that are found not to be in compliance with all Federal, State or Municipal building codes. The landscape architect is not responsible for discrepancies discovered by the final inspection for the certificate of occupancy or Federal, State or Municipal inspections / approvals that were not identified at the time that the permits were issued by Federal, State or Municipal officials for the project.
3. The contractor shall follow and be guided by OSHA safety regulations. Contractor shall furnish to owner and landscape architect a certificate of insurance prior to start of work. The landscape architect shall not have control over or change of and shall not be responsible for construction means, safety precautions, and safety programs in conjunction with the work. These are solely the contractor's responsibility.
4. Existing site conditions: The contractor shall thoroughly investigate all site conditions and take field measurements prior to the start of work. Field check all measurements, existing and proposed topography prior to the start of work. Check and verify all existing dimensions on job site.
5. All proposed improvements shall be laid out in the field by a NJ licensed surveyor prior to construction.
6. Contractor shall notify the landscape architect of any discrepancy in the plans or specification before proceeding with any work related to or affected by the discrepancy or error. Give 72-hour notice prior to the need for additional information or for clarification.
7. Written dimensions govern. Do not scale drawing. Specifications govern drawings.
8. The property owner shall submit these drawings for municipal approval before commencing ANY CONSTRUCTION!!! The landscape architect shall not be responsible or liable for any adjustments to the drawings, materials, site work, walls, pools, structures, fences, buildings, plantings, etc., if required by regulation compliance or changes made by owner after construction has started.
9. Locate, determine the depth of, and be responsible for all underground utilities prior to start of work / construction. The contractor is responsible for all repairs to any underground or overhead utility damaged by him or his sub-contractor during construction. It is illegal to perform excavation without a proper markout performed by a qualified agency. Within NJ call 1-800-272-1000.
- Septic system: Contractor shall locate septic system and septic laterals and protect them during construction. Do not park equipment on or drive across these areas.
10. At the commencement of the project, the contractor shall furnish the owner and landscape architect with a time schedule for the completion of the various phases of the proposed work. Contractor shall keep the owner and the landscape architect notified of schedule changes.
- The landscape architect shall not be responsible for the contractor's schedules or ability to carry out the work in accordance with the plans and specifications. The landscape architect shall have no control over or charge of acts or omissions of the contractor, subcontractor or their agents or employees or other persons performing portions of their work.

11. Site protection: Protect lawns, meadows, buildings and existing trees & shrubs from construction damage. Do not park equipment or stockpile materials on lawn, meadow or within the root zone/drip line of trees areas. Tree protection fencing shall be provided around all existing trees to be save that are within the work zone. Contractor is responsible for the repair of any damage outside of work area.
 12. Site clean up and debris removal: At the completion of each phase, the contractor is responsible to remove his own debris. Cost of such removal shall be included in cost estimates. AT ALL TIMES, JOB SITE SHALL BE KEPT NEAT AND CLEAN!!!!!!!!!!!!!!
 13. Topsoil. Supply source and sample of topsoil at the time of the bid submission. Spread topsoil 12"-18" (for larger shrubs make 4" deeper than root ball) deep in all plant bed areas and 4" in all lawn areas. Excavate plant bed areas as required in order to facilitate the installation of topsoil and drainage.
 14. Contractor is responsible for removing and or supplying fill dirt or topsoil as may be required for the project. Do not dispose of excess fill material on site.
 15. The landscape architect shall not be responsible for maintenance, or possible removal of the following items from the project site which may be discovered during the course of excavation, demolition and construction:
 - a: Underground drainage systems, storage tanks, utilities, and/or septic systems.
 - b: Asbestos, lead, or any other material classified as hazardous.
 - c: Buried debris or trash.Upon discovery the contractor shall not disturb or damage any of the above mentioned items; but shall notify the owner immediately of the above-mentioned situation. Furthermore, the contractor shall proceed with arranging for all inspections and for hiring appropriate licensed professionals as required to rectify the discovered problem. The contractor shall advise the owner of all extra costs before proceeding with the work, and shall obtain approvals from all regulatory agencies.
 16. The Client acknowledges and agrees that proper project maintenance is required after the project is complete. A lack of or improper maintenance may result in damage to property or persons. Client further acknowledges that, as between the parties to this agreement, client is solely responsible for the results of any lack of or improper maintenance.
 17. The Client is responsible for the determining and delineating all wetlands, streams and their associated buffers.
- LAWN SEEDING SPECIFICATIONS:
1. Ground preparation:
Area to be seeded must be fnable to a depth of 4" and contain no debris of any kind; including but not limited to clumps, branches, stones, wood construction debris, rubbish and dead plant material. Debris over 1 1/2" dia. are a "must remove" item. After soil is prepared no heavy equipment shall be moved over the area.
 2. Lime to be added to the soil at a rate of 2 tons per acre or as dictated by soil tests.
 3. Apply starter fertilizer such as 18-24-12 at a rate of 5 lb. per 1000 sq. ft; incorporate into the top three inches of the soil.
 4. Seed at the rate of 6 lb. per 1000 sq. ft in all lawn areas. Contractor shall use FM Brown's, Inc. (800-334-8816) www.fmbrown.com "Green Turf Sun & Shade Mixture" seed mix or equal with 25% perennial rye grass blend added. Seed to be incorporated into the soil by 1/16" - 1/8" by dragging or raking.
 5. Straw mulch at a rate of 2-2 1/2 tons per acre. Straw mulch or equal shall be applied by the means of a mechanical mulcher. Tack Straw as required to stabilize.
 6. Produce dense, vigorous, well-established grass areas. Reseed areas as required. Owner is responsible for proper watering to ensure turf establishment.
 7. Once established, the lawn, shall be mowed to a height of 4" to allow for dense root growth.




KEY MAP
[SOURCE: Neamap 9/14/23]

R-1 - RESIDENCE
R-4 - RESIDENCE
RR - RURAL RESIDENTIAL
PL - PUBLIC LAND

SHEET INDEX

COVER SHEET	L-001
EXISTING CONDITIONS & DEMO PLAN	L-100
GRADING PLAN	L-101
CONSTRUCTION DETAILS	L-500
SESC DETAILS	L-501
SESC NOTES	L-502



WARNING:
If this drawing does not contain a raised seal impression and an original signature by the professional it is not an original document. It may have been altered and should not be used for construction.

SOURCE INFORMATION:
Base Information Provided By:
Parker Engineering & Surveying P.C.
370 East Main Street
Somerville, NJ 08876
(908) 729-4400

88 GLEN ALPIN ROAD, LLC
HARDING TOWNSHIP, NEW JERSEY


COVER SHEET

PREPARED FOR:
88 GLEN ALPIN ROAD, LLC
LOT 11, BLOCK 26
88 GLEN ALPIN ROAD
HARDING TOWNSHIP, NJ
PREPARED BY:
BOSENBERG
LANDSCAPE ARCHITECTURE
PO BOX 486
FAR HILLS, NJ 07931
(908)234-0557
DATE: DECEMBER 18, 2023
SCALE: AS NOTED
REVISIONS:

NJ Certificate of Authorization
MH000126
JIM MAZZUCCO
NEW JERSEY LICENSED
LANDSCAPE ARCHITECT
#A5500880

Jim Mazzucco
SHEET **L-001**

Know what's below.
Call before you dig. **811**
1-800-272-1000



TREE REMOVAL LEGEND

- # EXISTING TREE TO REMAIN
- ✕ # EXISTING TREE TO BE REMOVED

TOTAL NUMBER OF TREES TO BE REMOVED: 18

EASEMENT LEGEND

- TREE CONSERVATION EASEMENT
- TREE PRESERVATION EASEMENT
- SIGHT EASEMENT
- SLOPE EASEMENT

TREE REMOVAL LIST		
ID	SIZE & SPECIES	STATUS
1	38" ELM	TO REMAIN
2	(3) 18" ELMS	TO REMAIN
3	14" WALNUT	TO REMAIN
4	12" MAPLE	TO REMAIN
5	(3) 20" ELMS	TO REMAIN
6	15" APPLE	TO REMAIN
7	(2) 6" DOGWOODS	TO REMAIN
8	24" ELM	TO REMAIN
9	6" HOLLY	TO REMAIN
12	28" EVERGREEN	TO REMAIN
16	3" HOLLY & 8" HOLLY	TO REMAIN
17	24" SASSAFRAS	TO REMAIN
18	20" EVERGREEN	TO REMAIN
19	8" SASSAFRAS	TO REMAIN
20	12" EVERGREEN	TO BE REMOVED
21	22" EVERGREEN	TO BE REMOVED
22	40" EVERGREEN	TO REMAIN
23	2" CHERRY	TO REMAIN
24	4" DOGWOOD	TO REMAIN
25	4" DOGWOOD	TO REMAIN
26	36" EVERGREEN	TO REMAIN
27	4" HOLLY	TO REMAIN
28	34" EVERGREEN	TO REMAIN
29	8" ASH	TO REMAIN
30	24" EVERGREEN	TO REMAIN
31	34" EVERGREEN	TO REMAIN
32	20" EVERGREEN	TO REMAIN
33	24" EVERGREEN	TO REMAIN
34	30" EVERGREEN	TO REMAIN
35	20" EVERGREEN	TO REMAIN
36	8" EVERGREEN	TO REMAIN
37	14" EVERGREEN	TO REMAIN
38	(3) 18" EVERGREENS	TO REMAIN
39	24" EVERGREEN	TO REMAIN
40	36" EVERGREEN	TO REMAIN
41	15" EVERGREEN	TO REMAIN
43	15" APPLE	TO BE REMOVED
44	4" FRUIT TREE	TO BE REMOVED
46	8" FRUIT TREE	TO BE REMOVED
48	12" EVERGREEN	TO BE REMOVED
49	12" EVERGREEN	TO BE REMOVED
50	16" ASH	TO BE REMOVED
51	18" OAK	TO BE REMOVED
52	56" OAK	TO REMAIN
53	15" OAK	TO REMAIN
54	8" OAK	TO REMAIN
55	12" OAK	TO REMAIN
56	24" OAK	TO REMAIN
57	15" OAK	TO REMAIN
58	20" OAK	TO REMAIN
59	6" EVERGREEN	TO REMAIN
60	36" OAK	TO REMAIN
61	24" MAPLE	TO BE REMOVED
62	20" ELM	TO REMAIN
63	6" BEECH	TO BE REMOVED
64	22" BEECH	TO BE REMOVED
65	8" DOGWOOD	TO BE REMOVED
69	15" ELM & 18" ELM	TO REMAIN
70	8" GUM	TO REMAIN
71	8" GUM	TO REMAIN
72	8" GUM	TO REMAIN
73	6" DOGWOOD	TO REMAIN
74	36" ELM	TO REMAIN
75	4" BIRCH	TO REMAIN
76	18" MAPLE	TO REMAIN
77	(2) 6" CHERRY	TO REMAIN
78	12" APPLE	TO REMAIN
79	APPLE CLUMP 12"	TO REMAIN
80	30" ELM	TO REMAIN
81	18" ELM	TO REMAIN
82	30" ELM	TO BE REMOVED
83	20" ELM	TO REMAIN
84	15" ELM	TO REMAIN
85	18" ELM	TO REMAIN
86	(4) 15" ELMS	TO REMAIN
87	22" ELM	TO REMAIN
88	6" EVERGREEN	TO BE REMOVED
89	10" EVERGREEN	TO BE REMOVED
90	10" ELM	TO BE REMOVED
91	8" EVERGREEN	TO BE REMOVED
92	SPRUCE CLUMP 30"	TO REMAIN
93	SPRUCE CLUMP 30"	TO REMAIN
104	24" ELM	TO REMAIN

WARNING:
If this drawing does not contain a raised seal impression and an original signature by the professional it is not an original document. It may have been altered and should not be used for construction.

SOURCE INFORMATION:
Base Information Provided By:
Parker Engineering & Surveying P.C.
20 East Main Street
Somerville, NJ 08876
(908) 725-4400

88 GLEN ALPIN ROAD, LLC
HARDING TOWNSHIP, NEW JERSEY


EXISTING CONDITIONS & DEMO PLAN
PREPARED FOR:
88 GLEN ALPIN ROAD, LLC
LOT 11, BLOCK 26
88 GLEN ALPIN ROAD
HARDING TOWNSHIP, NJ
PREPARED BY:
BOSENBERG
LANDSCAPE ARCHITECTURE
PO BOX 486
FAR HILLS, NJ 07931
(908) 234-0557
DATE: DECEMBER 18, 2023
SCALE: 1" = 20'
REVISIONS:

NJ Certificate of Authorization
MH000126
JIM MAZZUCCO
NEW JERSEY LICENSED
LANDSCAPE ARCHITECT
#AS000800

SHEET **L-100**



EASEMENT LEGEND



Lot Area	105,611	sf.
Allowable Lot Coverage (10%)	10,561.10	sf.
Lot Coverage Calculations		
Proposed Residence	2,030.00	sf.
Front walk	70.00	sf.
Walk (side)	93.00	sf.
Patio (main house)	251.00	sf.
Proposed Driveway	4,210.00	sf.
Existing Garage	544.46	sf.
Proposed Garage Addition	212.00	sf.
Proposed Pool	880.00	sf.
Proposed Pool patio and walks	646.46	sf.
Existing Cottage	920.25	sf.
Existing Shed	574.35	sf.
Misc. steps, landing	24.00	sf.
Utilities (ac, generator)	68.00	sf.
Total Proposed Lot Coverage:	10,523.52	(9.96%)


Building Coverage Calculations		
Proposed Residence	2,030.00	sf.
Existing Garage	544.46	sf.
Proposed Garage Addition	212.00	sf.
Existing Shed	574.35	sf.
Existing Cottage	920.25	sf.
Proposed Building Coverage:	4,281.06	(4.05%)

Slopes Table				
Number	Minimum Slope	Maximum Slope	Color	SF.
1	0.00%	7.90%		46,196.12
2	8.00%	11.90%		40,910.41
3	12.00%	15.90%		11,137.06
4	16.00%	19.90%		3,461.28
5	20.00%	24.90%		807.04
6	25.00%	29.90%		309.52
7	30.00%	100.00%		464.20

Slope Category	Total Area (sf.)	Disturbed Area (sf.)	Slope Adjustment Factor	Adjusted Graded Area (sf.)
0% - 7.9%	46,521.49	16,421.2	1.0	16,421.2
8% - 11.9%	40,910.41	6,428.6	1.5	9,643.0
12% - 15.9%	11,137.06	1,776.4	2.6	4,618.5
16% - 19.9%	3,461.28	544.0	3.8	2,067.2
20% - 24.9%	807.04	-	5.5	-
25% - 29.9%	309.52	-	7.5	-
30% or Greater	464.20	67.3	8.6	578.8
				33,328.7

PLANT SCHEDULE: TREE REPLACEMENT PLAN


KEY	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER
TREES					
ACE OCT	3	Acer rubrum 'October Glory'	October Glory Red Maple	3"-3.5" cal.	B#B
CEL OCC	1	Celtis occidentalis	Common Hackberry	3"-3.5" cal.	B#B
JUN VIR	2	Juniperus virginiana	Eastern Redcedar	8"-10"	B#B
NYS SYL	3	Nyssa sylvatica	Tupelo	3"-3.5" cal.	B#B
PIC ABI	3	Picea abies	Norway Spruce	8"-10"	B#B
PIN STR	2	Pinus strobus	White Pine	8"-10"	B#B
QUE BIC	2	Quercus bicolor	Swamp White Oak	3"-3.5" cal.	B#B
QUE PAL	1	Quercus palustris	Pin Oak	3"-3.5" cal.	B#B
QUE PHE	1	Quercus phellos	Willow Oak	3"-3.5" cal.	B#B



WARNING:
If this drawing does not contain a raised seal impression and an original signature by the professional, it is not an original document. It may have been altered and should not be used for construction.

SOURCE INFORMATION:
Base Information Provided By:
Parker Engineering & Surveying P.C.
270 East Main Street
Somerville, NJ 08876
(908) 729-4400
Architectural Information Provided By:
Siti Milburn Ave.
Sheet Hills, NJ 07079
(973) 376-5111

88 GLEN ALPIN ROAD, LLC
HARDING TOWNSHIP, NEW JERSEY




GRADING PLAN

PREPARED FOR:
88 GLEN ALPIN ROAD, LLC
LOT 11 BLOCK 26
88 GLEN ALPIN ROAD
HARDING TOWNSHIP, NJ
PREPARED BY:
BOSENBERG
LANDSCAPE ARCHITECTURE
PO BOX 486
FAR HILLS, NJ 07931
(908) 234-0557

DATE: DECEMBER 18, 2023
SCALE: 1" = 20'
REVISIONS:

NJ Certificate of Authorization
MH000126
JIM MAZZUCCO
NEW JERSEY LICENSED
LANDSCAPE ARCHITECT
#A5500800



Jim Mazzucco
SHEET **L-101**




88 GLEN ALPIN ROAD, LLC
HARDING TOWNSHIP, NEW JERSEY


ificate of Authorization
26
ZUCCO
RSEY LICENSED
CAPE ARCHITECT
0800

ET L-500



SCALE: 3/4" = 1'-0"







1. FENCE POST TO BE PLACED 8 FEET CENTER TO CENTER OR CLOSER. THEY SHALL EXTEND AT LEAST 2 FEET INTO THE GROUND AND 2 FEET ABOVE GROUND. POSTS SHALL BE CONSTRUCTED OF HARDWOOD WITH A MINIMUM THICKNESS OF 1 1/2".
2. A METAL FENCE WITH 6" OR SMALLER OPENINGS AND AT LEAST 2 FEET HIGH MAY BE UTILIZED, FASTENED TO THE FENCE POSTS, TO PROVIDE REINFORCEMENT AND SUPPORT TO THE GEOTEXTILE FABRIC WHERE SPACE FOR THE PRACTICES IS LIMITED AND HEAVY SEDIMENT LOADING IS EXPECTED.
3. A GEOTEXTILE FABRIC, RECOMMENDED FOR SUCH USE BY THE MANUFACTURER, SHALL BE BURIED AT LEAST 6 INCHES DEEP IN THE GROUND. THE FABRIC SHALL EXTEND AT LEAST 2 FEET ABOVE THE GROUND. THE FABRIC MUST BE SECURELY FASTENED TO THE POSTS USING A SYSTEM CONSISTING OF METAL FASTENERS (NAILS OR STAPLES) AND A HIGH STRENGTH REINFORCEMENT MATERIAL (NYLPN WEBBING, GROMMETS, WASHERS) PLACED BETWEEN THE FABRIC AND THE FASTENER. THE FASTENING SYSTEM SHALL RESIST TEARING AWAY FRO THE POST. THE FABRIC SHALL INCORPORATE A DRAWSTRING IN THE TOP PORTION OF THE FENCE FOR ADDED STRENGTH.

SILT FENCE

NOT TO SCALE




PROFILE VIEW



PLAN VIEW

TRACKING PAD

NOT TO SCALE



INLET FILTER DETAIL

NOT TO SCALE

SOIL STOCKPILE DETAIL

NO SCALE

Soil De-compaction and Testing Requirements

Soil Compaction Testing Requirements

1. Subgrade soils **prior to the application of topsoil** (see permanent seeding and stabilization notes for topsoil requirements) shall be free of excessive compaction to a depth of 6.0 inches to enhance the establishment of permanent vegetative cover.
2. Areas of the site which are subject to compaction testing and/or mitigation are **graphically denoted** on the certified soil erosion control plan.
3. **Compaction testing locations** are denoted on the plan. A copy of the plan or portion of the plan shall be used to mark locations of tests, and attached to the compaction mitigation verification form, available from the local soil conservation district. This form must be filled out and submitted prior to receiving a certificate of compliance from the district.
4. In the event that testing indicates compaction in excess of the maximum thresholds indicated for the simplified testing methods (see details below), the contractor/owner shall have the option to perform either (1) compaction mitigation over the entire mitigation area denoted on the plan (excluding exempt areas), or (2) perform additional, more detailed testing to establish the limits of excessive compaction whereupon only the excessively compacted areas would require compaction mitigation. Additional detailed testing shall be performed by a trained, licensed professional.

Compaction Testing Methods

- A. Probing Wire Test (see detail)
- B. Hand-held Penetrometer Test (see detail)
- C. Tube Bulk Density Test (licensed professional engineer required)
- D. Nuclear Density Test (licensed professional engineer required)

Note: Additional testing methods which conform to ASTM standards and specifications, and which produce a dry weight, soil bulk density measurement may be allowed subject to District approval.

Soil compaction testing is not required if/when subsoil compaction remediation (scarification/tillage (6" minimum depth) or similar) is proposed as part of the sequence of construction.

Procedures for Soil Compaction Mitigation


Procedures shall be used to mitigate excessive soil compaction **prior to placement of topsoil** and establishment of permanent vegetative cover.

Restoration of compacted soils shall be through deep scarification/tillage (6" minimum depth) where there is no danger to underground utilities (cables, irrigation systems, etc.). In the alternative, another method as specified by a New Jersey Licensed Professional Engineer maybe substituted subject to District Approval.

Simplified Testing Methods


Probing Wire Test- 15.5 ga steel wire (survey flag)

Note: soil should be moist but not saturated. Do not test when soil is excessively dry or subject to freezing temperatures. Slow, steady downward pressure used to advance the wire.



Handheld Soil Penetrometer Test

Note: soil should be moist but not saturated. Do not test when soil is excessively dry or subject to freezing temperatures. Slow, steady downward pressure used to advance the probe. Probe must penetrate at least 6" with less than 300 psi reading on the gauge.



88 GLEN ALPIN ROAD, LLC
HARDING TOWNSHIP, NEW JERSEY

SESC DETAILS

PREPARED FOR:
88 GLEN ALPIN ROAD, LLC
LOT 11, BLOCK 26
88 GLEN ALPIN ROAD
HARDING TOWNSHIP, NJ
PREPARED BY:
BOSENBERG
LANDSCAPE ARCHITECTURE
PO BOX 486
FAR HILLS, NJ 07931
(908)234-0557
DATE: DECEMBER 18, 2023
SCALE: AS NOTED
REVISIONS:

NJ Certificate of Authorization
MH000126
JIM MAZZUCCO
NEW JERSEY LICENSED
LANDSCAPE ARCHITECT
#A5304800

Jim Mazzucco
SHEET **L-501**

SOIL EROSION AND SEDIMENT CONTROL NOTES
MORRIS COUNTY SOIL CONSERVATION DISTRICT

SEQUENCE OF CONSTRUCTION

The Somerset - Union Soil Conservation District shall be notified at least 48 hours in advance of beginning of project and upon completion of permanent stabilization of all disturbed areas.

1. Install all soil erosion and sediment control (SESC) plan requirements as specified on-plan (page L-100); including stabilized construction access, silt fencing and soil erosion and sediment control measures, as well as tree protection where applicable. (1 week)
2. Clear site, strip and stockpile soil. (1 week)
3. Trench for utilities, schedule inspection. (3 weeks)
4. Grade sub-base in preparation for installation of hardscape elements. (1 week)
5. Construction of on site improvements. (2 weeks)
6. Fine grade disturbed areas, scarify top 6" of sub-base soil, perform compaction test. (1 week)
7. Install 5" of topsoil, seed lawn areas, install landscaping and permanent stabilization. (3 days)
8. Remove temporary silt fence, inlet protection and other soil erosion controls. (1 day)

STANDARD FOR DUST CONTROL

Applicable to areas subject to dust blowing and movement where on-site and off-site damage is likely without treatment. Consult with local municipal ordinances on any restrictions.

Planning Criteria: The following methods should be considered for controlling dust:

Mulches - See Standard of Stabilization with Mulches Only, pg. 5-1

Vegetative Cover - See Standard for: Temporary Vegetative Cover, pg. 7-1, Permanent Vegetative Cover for Soil Stabilization pg. 4-1 and Permanent Stabilization with Sod, pg. 6-1

Spray-On Adhesives - On mineral soils (not effective on muck soils). Keep traffic off these areas.

Table 16-1: Dust Control

Material	Water Dilution	Type of nozzle	Apply Gal./acre
Anionic asphalt emulsion	7:1	Coarse spray	1200
Latex emulsion	12.5:1	Fine spray	235
Resin in water	4:1	Fine spray	300
Polyacrylamide(PAM)-spray on Polyacrylamide (PAM)- dry spray	Apply according to manufacturer's instructions. May also be used as an additive to sediment Basins to flocculate and precipitate suspended colloids. See Sediment Basin Standards (pg26-1)		
Acidulated Soy Bean Soap Stick		Coarse spray	1200

Tillage - To roughen surface and bring clods to the surface. This is a temporary emergency measure which should be used before soil blowing starts. Begin plowing on windward side of site. Chisel-type plows spaced about 12 inches apart and spring-toothed harrows are examples of equipment which may produce the desired effect.

Sprinkling - Site is sprinkled until the surface is wet.

Barriers - Solid board fences, snow fences, burlap fences, crate walls, bales of hay and similar material can be used to control air currents and soil blowing.

Calcium Chloride - Shall be in the form of loose, dry granules or flakes fine enough to feed through commonly used spreaders at a rate that will keep surface moist but not cause pollution or plant damage. If used on steeper slopes, then use other practices to prevent washing into streams or accumulation around plants.

Stone - Cover surface with crushed stone or coarse gravel.

STANDARD FOR PERMANENT VEGETATIVE COVER FOR SOIL STABILIZATION

Applicable on exposed soils that have a potential for causing off-site environmental damage.

1. Site Preparation
 - A. Grade as needed and feasible to permit the use of conventional equipment for seedbed preparation, seeding, mulch application, and mulch anchoring. All grading should be done in accordance with Standard for Land Grading.
 - B. Immediately prior to seeding and topsoil application, the subsoil shall be evaluated for compaction in accordance with the Standard for Land Grading.
 - C. Topsoil should be handled only when it is dry enough to work without damaging the soil structure. A uniform application to a depth of 5 inches (unsettled) is required on all sites. Topsoil shall be amended with organic matter, as needed, in accordance with the Standard for Topsoiling.
 - D. Install needed erosion control practices or facilities such as diversions, grade-stabilization structures, channel stabilization measures, sediment basins, and waterways.
2. Seedbed Preparation
 - A. Uniformly apply ground limestone and fertilizer to topsoil which has been spread and firmed, according to soil test recommendations such as offered by Rutgers Co-operative Extension. Soil sample mailers are available from the local Rutgers Cooperative Extension offices (<http://njaes.rutgers.edu/county/>). Fertilizer shall be applied at the rate of 500 pounds per acre or 11 pounds per 1,000 square feet of 10-10-10 or equivalent with 50% water insoluble nitrogen unless a soil test indicates otherwise and incorporated into the surface 4 inches. If fertilizer is not incorporated, apply one-half the rate described above during seedbed preparation and repeat another one-half rate application of the same fertilizer within 3 to 5 weeks after seeding.
 - B. Work lime and fertilizer into the topsoil as nearly as practical to a depth of 4 inches with a disc, spring-tooth harrow, or other suitable equipment. The final harrowing or disking operation should be on the general contour. Continue tillage until a reasonable uniform seedbed is prepared.
 - C. High acid producing soil. Soils having a pH of 4 or less or containing iron sulfide shall be covered with a minimum of 12 inches of soil having a pH of 5 or more before initiating seedbed preparation. See Standard for Management of High Acid-Producing Soils for specific requirements.
3. Seeding
 - A. Select a mixture from Table 4-3 or use a mixture recommended by Rutgers Cooperative Extension or Natural Resources Conservation Service which is approved by the Soil Conservation District. Seed germination shall have been tested within 12 months of the planting date. No seed shall be accepted with a germination test date more than 12 months old unless retested.
 1. Seeding rates specified are required when a report of compliance is requested prior to actual establishment of permanent vegetation. Up to 50% reduction in rates may be used when permanent vegetation is established prior to a report of compliance inspection. These rates apply to all methods of seeding. Establishing permanent vegetation means 80% vegetative coverage with the specified seed mixture for the seeded area and mowed once.
 2. Warm-season mixtures are grasses and legumes which maximize growth at high temperatures, generally 85o F and above. See Table 4-3 mixtures 1 to 7. Planting rates for warm-season grasses shall be the amount of Pure Live Seed (PLS) as determined by germination testing results.
 3. Cool-season mixtures are grasses and legumes which maximize growth at temperatures below 85 degrees F. Many grasses become active at 65 degrees F. See Table 4-3, mixtures 8-20. Adjustment of planting rates to compensate for the amount of PLS is not required for cool season grasses.
 - B. Conventional Seeding is performed by applying seed uniformly by hand, cyclone (centrifugal) seeder, drop seeder, drill or cultipacker seeder. Except for drilled, hydroseeded or cultipacked seedings, seed shall be incorporated into the soil within 24 hours of seedbed preparation to a depth of 1/4 to 1/2 inch, by raking or dragging. Depth of seed placement may be 1/4 inch deeper on coarse-textured soil.
 - C. After seeding, firming the soil with a corrugated roller will assure good seed-to-soil contact, restore capillarity, and improve seedling emergence. This is the preferred method. When performed on the contour, sheet erosion will be minimized and water conservation on site will be maximized.
 - D. Hydroseeding is a broadcast seeding method usually involving a truck, or trailer-mounted tank, with an agitation system and hydraulic pump for mixing seed, water and fertilizer and spraying the mix onto the prepared seedbed. Mulch shall not be included in the tank with seed. Shortfibered mulch may be applied with a hydroseeder following seeding. (also see Section 4-Mulching below). Hydroseeding is not a preferred seeding method because seed and fertilizer are applied to the surface and not incorporated into the soil. When poor seed to soil contact occurs, there is a reduced seed germination and growth.
4. Mulching

Mulching is required on all seeding. Mulch will protect against erosion before grass is established and will promote faster and earlier establishment. The existence of vegetation sufficient to control soil erosion shall be deemed compliance with this mulching requirement.

- A. Straw or Hay. Unrotted small grain straw, hay free of seeds, to be applied at the rate of 1-1/2 to 2 tons per acre (70 to 90 pounds per 1,000 square feet), except that where a crimper is used instead of a liquid mulch-binder (tackifying or adhesive agent), the rate of application is 3 tons per acre. Mulch chopper-blowers must not grind the mulch. Hay mulch is not recommended for establishing fine turf or lawns due to the presence of weed seed. Application - Spread mulch uniformly by hand or mechanically so that at least 85% of the soil surface is covered. For uniform distribution of hand-spread mulch, divide area into approximately 1,000 square feet sections and distribute 70 to 90 pounds within each section. Anchoring shall be accomplished immediately after placement to minimize loss by wind or water. This may be done by one of the following methods, depending upon the size of the area, steepness of slopes, and costs.
 1. Peg and Twine. Drive 8 to 10 inch wooden pegs to within 2 to 3 inches of the soil surface every 4 feet in all directions. Stakes may be driven before or after applying mulch. Secure mulch to soil surface by stretching twine between pegs in a criss-cross and a square pattern. Secure twine around each peg with two or more round turns.
 2. Mulch Nettings - Staple paper, jute, cotton, or plastic nettings to the soil surface. Use a degradable netting in areas to be mowed.
 3. Crimper (mulch anchoring coultter tool) - A tractor-drawn implement, somewhat like a disc harrow, especially designed to push or cut some of the broadcast long fiber mulch 3 to 4 inches into the soil so as to anchor it and leave part standing upright. This technique is limited to areas traversable by a tractor, which must operate on the contour of slopes. Straw mulch rate must be 3 tons per acre. No tackifying or adhesive agent is required.
 4. Liquid Mulch-Binders - May be used to anchor salt hay, hay or straw mulch.
 - a. Applications should be heavier at edges where wind may catch the mulch, in valleys, and at crests of banks. The remainder of the area should be uniform in appearance.
 - b. Use one of the following:
 - (1) Organic and Vegetable Based Binders - Naturally occurring, powder-based, hydrophilic materials when mixed with water formulates a gel and when applied to mulch under satisfactory curing conditions will form membraned networks of insoluble polymers. The vegetable gel shall be physiologically harmless and not result in a phytotoxic effect or impede growth of turf grass. Use at rates and weather conditions as recommended by the manufacturer to anchor mulch materials. Many new products are available, some of which may need further evaluation for use in this state.
 - (2) Synthetic Binders - High polymer synthetic emulsion, miscible with water when diluted and, following application of mulch, drying and curing, shall no longer be soluble or dispersible in water. Binder shall be applied at rates recommended by the manufacturer and remain tacky until germination of grass. Note: All names given above are registered trade names. This does not constitute a recommendation of these products to the exclusion of other products.
- B. Wood-fiber or paper-fiber mulch - shall be made from wood, plant fibers or paper containing no growth or germination inhibiting materials, used at the rate of 1,500 pounds per acre (or as recommended by the product manufacturer) and may be applied by a hydroseeder. Mulch shall not be mixed in the tank with seed. Use is limited to flatter slopes and during optimum seeding periods in spring and fall.
- C. Pelletized mulch - compressed and extruded paper and/or wood fiber product, which may contain co-polymers, tackifiers, fertilizers, and coloring agents. The dry pellets, when applied to a seeded area and watered, form a mulch mat. Pelletized mulch shall be applied in accordance with the manufacturer's recommendations. Mulch may be applied by hand or mechanical spreader at the rate of 80-15 lbs/1,000 square feet and activated with 0.2 to 0.4 inches of water. This material has been found to be beneficial for use on small lawn or renovation areas, seeded areas where weedseed free mulch is desired, or on sites where straw mulch and tackifier agent are not practical or desirable. Applying the full 0.2 to 0.4 inches of water after spreading pelletized mulch on the seed bed is extremely important for sufficient activation and expansion of the mulch to provide soil coverage.

5. Irrigation (where feasible)

If soil moisture is deficient supply new seeding with adequate water (a minimum of 1/4 inch applied up to twice a day until vegetation is well established). This is especially true when seedlings are made in abnormally dry or hot weather or on droughty sites.
6. Topdressing

Since soil organic matter content and slow release nitrogen fertilizer (water insoluble) are prescribed in Section 2A - Seedbed Preparation in this Standard, no follow-up of topdressing is mandatory. An exception may be made where gross nitrogen deficiency exists in the soil to the extent that turf failure may develop. In that instance, topdress with 10-10-10 or equivalent at 300 pounds per acre or 7 pounds per 1,000 square feet every 3 to 5 weeks until the gross nitrogen deficiency in the turf is ameliorated.
7. Establishing Permanent Vegetative Stabilization

The quality of permanent vegetation rests with the contractor. The timing of seeding, preparing the seedbed, applying nutrients, mulch and other management are essential. The seed application rates in Table 4-3 are required when a Report of Compliance is requested prior to actual establishment of permanent vegetation. Up to 50% reduction in application rates may be used when permanent vegetation is established prior to requesting a Report of Compliance from the district. These rates apply to all methods of seeding. Establishing permanent vegetation means 80% vegetative cover (of the seeded species) and mowed once. Note this designation of mowed once does not guarantee the permanency of the turf should other maintenance factors be neglected or otherwise mismanaged.

Harding Township
Soil Erosion and Sediment Control Notes

GENERAL NOTES:

1. All Soil erosion and -Sediment Control Practices Will be installed in accordance with the Standards for Soil Erosion and Sedimentation Control in the State of New Jersey, and will be in place prior to any major soil disturbance, or in their proper sequence and maintained until permanent protection is established.
2. Any disturbed area that will be left exposed for more than thirty (30) days and not subject to construction traffic shall immediately receive a temporary seeding. If the season prohibits temporary seeding, the disturbed area will be mulched with straw or hay and tacked in accordance with the New Jersey Standards. See Note 21 below.
3. Permanent vegetation is to be established on exposed areas within ten (10) days after final grading. Mulch is to be used for protection until vegetation is established. See Note 22 below.
4. Immediately following initial disturbance or rough grading. All critical areas (steep slopes, sandy soils, wet conditions) subject to erosion will receive temporary seeding in accordance with Note 21 below.
5. Temporary Diversion Berms are to be installed on all cleared roadways and easement areas in accordance with Section 4:21 of the State Standards.
6. Permanent seeding and stabilization to be in accordance with the Standards for Permanent Vegetative Cover. Specified rates and locations shall be on the approved Soil Erosion and Sedimentation Control Plan.
7. The site shall at all times be graded and maintained so that all storm water runoff is diverted to Soil Erosion and Sedimentation Control facilities.
8. All sedimentation structures (silt fence, inlet filters, and sediment basins) will be inspected and maintained daily.
9. Stockpiles shall not be located within 50' of a floodplain, slope, drainage facility or roadway. All stockpile bases shall be protected by a silt fence.
10. A crushed stone, vehicle wheel-cleaning blanket (stabilized construction access) will be installed per the detail.
11. All new roadways will be treated suitable subbase upon establishment of final grade elevations.
12. Paved roadways must be kept clean at all times.
13. All catch basin inlets will be protected in accordance with the inlet filter detail provided on the plans.
14. Before discharge points become operational, all storm drainage outlets will be stabilized as required.
15. All dewatering operations must be discharged directly into a sediment filter area. The sediment filter should be composed of a suitable sediment fabric. See the Dewatering detail.
16. All sedimentation basins will be cleaned when the capacity has been reduced by 50%. A clean out elevation will be identified on the plan and a marker installed on the site.
17. During and after construction the owner will be responsible for the maintenance and upkeep of the drain structures, vegetation cover, and any other measures deemed appropriate by the Township Engineer. Said responsibility will preclude when all work is approved by the Township Engineer.
18. All trees to remain after construction are to be protected with tree protection devices. See the Tree Protection detail.
19. The Township Engineer may request additional measures to minimize on site or off site erosion problems during construction.
20. The Township Engineer must be notified, in writing, at least 72 hours prior to any land

TOP SOIL STOCKPILE PROTECTION

1. Construct temporary diversion berm and/or hay bale barrier around stockpile area as required.
2. Apply limestone at a rate of 90 lbs./1000 S.F.
3. Apply fertilizer (10-20-10) at a rate of 11 lbs. / 1000 S.F.
4. Apply perennial Ryegrass at a rate of 1 lb/1000 S.F. and Annual Ryegrass at a rate of 1lb/1000 S.F.
5. Mulch with unrotted salt hay or small grain straw immediately after seeding. Apply at a rate of 90 lbs./1000 S.F.
6. Apply liquid mulch binder or tack to straw or hay mulch

TEMPORARY STABILIZATION SPECIFICATIONS

1. Apply ground limestone at a rate of 90 lbs./1000 S.F.
2. Apply fertilizer (10-20-10) at a rate of 11 lbs. / 1000 S.F. and work into soil 4" deep.
3. Apply seed mixture.

Perennial Ryegrass at a rate of 40 lbs./acre and Annual Ryegrass at 40 lbs./acre or approved equal.
4. Mulch with unrotted salt hay or small grain straw immediately after seeding. Apply at a rate of 90 lbs./1000 S.F. and secure by applying a liquid mulch binder or tack to straw or hay mulch.
5. Plant seed between March 1 4 May 15 or between Aug. 15 4 Oct. 1, if possible

PERMANENT STABILIZATION SPECIFICATIONS

1. Apply topsoil to a depth of 5" (loose).
2. Apply ground limestone at a rate of 90 lbs./1000 S.F. and work 4" into soil.
3. Apply fertilizer (10-20-10) at a rate of 11 lbs. / 1000 S.F. and work into soil 4" deep.
4. Apply seed mixture.

Perennial Ryegrass at a rate of 10 lbs./acre, Kentucky Bluegrass at a rate of 25 lbs./acre, Red Fescue at 15 lbs./acre or approved equal.
5. Mulch with unrotted salt hay or small grain straw immediately after seeding. Apply at a rate of 90 lbs./1000 S.F. and secure by applying a liquid mulch binder or tack to straw or hay mulch. If possible, plant seed between March 1 4 May 15 or between Aug. 15 4 Oct. 1.

NOTE: 72 HOURS PRIOR TO ANY SOIL DISTURBANCE, NOTICE OF SUCH IN WRITING SHALL BE GIVEN TO THE TOWNSHIP ENGINEER.

88 GLEN ALPIN ROAD, LLC
HARDING TOWNSHIP, NEW JERSEY


SESC NOTES

PREPARED FOR:
88 GLEN ALPIN ROAD, LLC
LOT 11 BLOCK 26
88 GLEN ALPIN ROAD
HARDING TOWNSHIP, NJ
PREPARED BY:
BOSENBERG
LANDSCAPE ARCHITECTURE
PO BOX 486
FAR HILLS, NJ 07931
(908)234-0557

DATE: DECEMBER 18, 2023
SCALE:
REVISIONS:


NJ Certificate of Authorization
MH000126
JIM MAZZUCCO
NEW JERSEY LICENSED
LANDSCAPE ARCHITECT
#AS0000000

Jim Mazzucco
SHEET **L-502**



01 EXISTING FIRST FLOOR PLAN

SCALE: 1/4" = 1'-0"



02 EXISTING SECOND FLOOR PLAN

SCALE: 1/4" = 1'-0"



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798

NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

RESIDENCE:
EXISTING FLOOR PLANS

Z-0.0



01 EXISTING FRONT ELEVATION
SCALE: 1/4" = 1'-0"



02 EXISTING RIGHT SIDE ELEVATION
SCALE: 1/4" = 1'-0"



03 EXISTING REAR ELEVATION
SCALE: 1/4" = 1'-0"



04 EXISTING LEFT SIDE ELEVATION
SCALE: 1/4" = 1'-0"



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798


NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ


RESIDENCE:
EXISTING ELEVATIONS

Z-0.1



01 PROPOSED FIRST FLOOR PLAN

SCALE: 1/4" = 1'-0"



02 PROPOSED SECOND FLOOR PLAN

SCALE: 1/4" = 1'-0"



studio 1200, LLC

511 MILLBURN AVENUE
SHORT HILLS, NJ 07078

973.376.5111

973.376.5011

www.studio1200.com

CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798

NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

RESIDENCE:
PROPOSED FLOOR PLANS

Z-1.0



01 PROPOSED FRONT ELEVATION
SCALE: 1/4" = 1'-0"



02 PROPOSED RIGHT SIDE ELEVATION
SCALE: 1/4" = 1'-0"

KEY NOTES:

- 01 NEW CLAPBOARD SIDING
- 02 NEW DOUBLE HUNG WINDOWS WITH 6/6 LITES
- 03 NEW STANDING SEAM COPPER ROOF
- 04 NEW CEDAR SHINGLE ROOF
- 05 NEW AZEK TRIM & COLUMNS
- 06 NEW DECORATIVE GABLE TRIM & CORBELS
- 07 NEW STONE VENEER



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798

NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

RESIDENCE:
PROPOSED FRONT AND
RIGHT SIDE ELEVATIONS

Z-1.1



01 PROPOSED REAR ELEVATION
SCALE: 1/4" = 1'-0"



02 PROPOSED LEFT SIDE ELEVATION
SCALE: 1/4" = 1'-0"

KEY NOTES:

- 01 NEW CLAPBOARD SIDING
- 02 NEW DOUBLE HUNG WINDOWS WITH 6/6 LITES
- 03 NEW STANDING SEAM COPPER ROOF
- 04 NEW CEDAR SHINGLE ROOF
- 05 NEW AZEK TRIM & COLUMNS
- 06 NEW DECORATIVE GABLE TRIM & CORBELS
- 07 NEW STONE VENEER



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798




NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

RESIDENCE:
PROPOSED REAR AND
LEFT SIDE ELEVATIONS

Z-1.2



01 EXISTING BASEMENT PLAN

SCALE: 1/4" = 1'-0"

02 EXISTING FIRST FLOOR PLAN

SCALE: 1/4" = 1'-0"

03 EXISTING ATTIC

SCALE: 1/4" = 1'-0"



studio 1200, LLC

511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798

NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

COTTAGE:
EXISTING FLOOR
PLANS

Z-2.0



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798




NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

COTTAGE:
EXISTING ELEVATIONS

Z-2.1





studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798




NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

COTTAGE:
PROPOSED FLOOR
PLANS

Z-3.0



01 PROPOSED BASEMENT PLAN
SCALE: 1/4" = 1'-0"

02 PROPOSED FIRST FLOOR PLAN
SCALE: 1/4" = 1'-0"

03 PROPOSED LOFT PLAN
SCALE: 1/4" = 1'-0"

KEY NOTES:

- 01 NEW CLAPBOARD SIDING
- 02 NEW DOUBLE HUNG WINDOWS WITH 6/6 LITES
- 03 NEW STANDING SEAM COPPER ROOF
- 04 NEW CEDAR SHINGLE ROOF
- 05 NEW AZEK TRIM & COLUMNS
- 06 NEW CARRIAGE STYLE GARAGE DOORS
- 07 NEW STONE VENEER




01 PROPOSED FRONT ELEVATION

SCALE: 1/4" = 1'-0"



02 PROPOSED RIGHT SIDE ELEVATION

SCALE: 1/4" = 1'-0"



03 PROPOSED REAR ELEVATION

SCALE: 1/4" = 1'-0"



04 PROPOSED LEFT SIDE ELEVATION

SCALE: 1/4" = 1'-0"

KEY NOTES:

- 01 NEW CLAPBOARD SIDING
- 02 NEW DOUBLE HUNG WINDOWS WITH 6/6 LITES
- 03 NEW STANDING SEAM COPPER ROOF
- 04 NEW CEDAR SHINGLE ROOF
- 05 NEW AZEK TRIM & COLUMNS
- 06 NEW CARRIAGE STYLE GARAGE DOORS
- 07 NEW STONE VENEER



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798

NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

COTTAGE:
PROPOSED ELEVATIONS

Z-3.1




01 EXISTING FRONT ELEVATION

SCALE: 1/4" = 1'-0"




02 EXISTING RIGHT SIDE ELEVATION

SCALE: 1/4" = 1'-0"




03 EXISTING FIRST FLOOR PLAN

SCALE: 1/4" = 1'-0"




04 EXISTING REAR ELEVATION

SCALE: 1/4" = 1'-0"



05 EXISTING LEFT SIDE ELEVATION

SCALE: 1/4" = 1'-0"



06 EXISTING ATTIC PLAN

SCALE: 1/4" = 1'-0"



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798

NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ


DETACHED GARAGE:
EXISTING PLANS &
ELEVATIONS

Z-4.0




01 PROPOSED FRONT ELEVATION

SCALE: 1/4" = 1'-0"



02 PROPOSED RIGHT SIDE ELEVATION

SCALE: 1/4" = 1'-0"




03 PROPOSED FIRST FLOOR PLAN

SCALE: 1/4" = 1'-0"




04 PROPOSED REAR ELEVATION

SCALE: 1/4" = 1'-0"



05 PROPOSED LEFT SIDE ELEVATION

SCALE: 1/4" = 1'-0"



06 PROPOSED SECOND FLOOR PLAN

SCALE: 1/4" = 1'-0"

KEY NOTES:

- 01 NEW CLAPBOARD SIDING
- 02 NEW DOUBLE HUNG WINDOWS WITH 6/6 LITES
- 03 NEW STANDING SEAM COPPER ROOF
- 04 NEW CEDAR SHINGLE ROOF
- 05 NEW AZEK TRIM & COLUMNS
- 06 NEW CARRIAGE STYLE GARAGE DOORS



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798


NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023


88 GLEN ALPIN ROAD
HARDING NJ

DETACHED GARAGE:
PROPOSED PLANS &
ELEVATIONS


Z-5.0




01 EXISTING FLOOR PLAN




02 EXISTING FRONT ELEVATION



03 EXISTING RIGHT SIDE ELEVATION



04 PROPOSED FRONT ELEVATION



05 PROPOSED RIGHT SIDE ELEVATION

KEY NOTES:

- 01 NEW CLAPBOARD SIDING
- 02 NEW DOUBLE HUNG WINDOWS WITH 6/6 LITES
- 03 NEW STANDING SEAM COPPER ROOF



studio 1200, LLC
511 MILLBURN AVENUE
SHORT HILLS, NJ 07078
973.376.5111
973.376.5011
www.studio1200.com
CERTIFICATE OF AUTHORIZATION # AC-710

Nancy Dougherty, AIA, LEED AP
NJ-AI 14861/NY-025099/CT-ARI.0011798

NOT FOR
CONSTRUCTION

NO	ISSUE	DATE
01	BOARD OF ADJUSTMENT	12.18.2023

88 GLEN ALPIN ROAD
HARDING NJ

SHED:
EXISTING & PROPOSED
PLAN & ELEVATIONS

Z-6.0